API NUMBER: 137 26994

Injection

Straight Hole

OKLAHOMA CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION P.O. BOX 52000 OKLAHOMA CITY, OK 73152-2000 (Rule 165:10-3-1)

Approval Date: 01/03/2013
Expiration Date: 07/03/2013

PERMIT TO DRILL

	5W County: STE		
SPOT LOCATION: W2 NW NE NW	SECTION LINES:	NORTH FROM WEST 330 1648	
Lassa Namas, SCHOOL LAND	Well No.		Well will be 200 feet from perset unit or less boundary
Lease Name: SCHOOL LAND	Well No:	SL-48	Well will be 330 feet from nearest unit or lease boundary.
Operator BANNER OIL & GAS LLC Name:		Telephone: 4058316700	OTC/OCC Number: 22792 0
BANNER OIL & GAS LLC			
PO Box 13178		RON SI	JTTON
Oklahoma City, OK	73113-1178	HC 64,	BOX 1975
Oklahoma City, Ok	73113-1176	LOCO	OK 73442
1 LOCO 2 3 4 5 Spacing Orders: No Spacing	800 Location Exception	6 7 8 9 10	Increased Density Orders:
Pending CD Numbers:			Special Orders:
			.,
Total Depth: 1150 Ground Elevation	Surface	Casing: 0	Depth to base of Treatable Water-Bearing FM: 50
Cement will be circulated from Tota	Denth to the Ground S	Surface on the Production	Casing String
Under Federal Jurisdiction: No	•	r Supply Well Drilled: No	Surface Water used to Drill: No
PIT 1 INFORMATION		Approved Method f	or disposal of Drilling Fluids:
Type of Pit System: ON SITE		A. Evaporation/de	water and backfilling of reserve pit.
Type of Mud System: WATER BASED		•	
Chlorides Max: 3000 Average: 2000		H 20 MII DITTIN	ER REQUIRED; CBL REQUIRED
Is depth to top of ground water greater than 10ft belo Within 1 mile of municipal water well? N Wellhead Protection Area? N	w base of pit? Y	TI. 20-WIL FIT LIN	EN NEGOTINED, OBE NEGOTINED
Pit is located in a Hydrologically Sensitive Are	a.		

Notes:

Category of Pit: 1A

Liner required for Category: 1A

Pit Location is ALLUVIAL

Pit Location Formation: ALLUVIUM

Description Category

ALTERNATE CASING

12/27/2012 - G71 - APPROVED WITH THE FOLLOWING CONDITIONS: 1) DRILLING FLUID WILL BE MUD PRIOR TO TOTAL DEPTH; AND, 2) A COPY OF THE CBL TO BE REVIEWED AND APPROVED BY OCC TECHNICAL STAFF PRIOR TO ANY COMPLETION WORK BEING

COMMENCED

SPACING 12/27/2012 - G75 - NA-INJECTION WELL

